

W *Westen Building Services ... From thought to finish*


74 Sanchez Avenue Ormond Beach Florida 32174

(617) 212-0020

Bayshore Bath & Tennis Club C/O Robert Hinkley
925 N. Halifax Avenue
Daytona Beach, FL 32118

January 21, 2024

[Proposal]



Bayshore Concrete Loading Dock:

- Excavate the existing brick/block from the loading dock platform.
- Remove all damaged concrete and pavers from stairs and ramp areas.
- Frame-in concrete forms in for new leveled concrete pour.
- Frame-in forms for new concrete stairs.
- Score the old existing concrete dock surface.
- Apply liquid latex bonding adhesive agent to all open concrete platform surfaces.
- Pour concrete leveling into the building and doorway with proper pitch for water run-off.
- Pour in new stairs leading to lower parking.
- Paint and reinstall aluminum railing for stairs.
- Build and install a new matching cable railing tying into existing and running over to stairs.
- Repair perimeter concrete blending it into the existing concrete loading dock.
- Paint perimeter of new loading dock.

Labor and building materials : \$ 8,790.00

***All debris generated by these projects will be removed and disposed of properly.*

Michael Westenhofer
Westen Building Services

SHAWNS CONCRETE

PROJECT PROPOSAL

Bayshore Towers Tennis Club
925 N. Halifax Avenue
Daytona Beach, FL 32118

Prepared Date:
on February 2, 2024

PROJECT DESCRIPTION

Shawn's concrete will provide materials and installation for the following.

1. Prepare the existing concrete to except the new poured concrete.
2. Form up for new loading dock height.
3. Remove paving stones from existing.
4. Pour new concrete over existing.
5. Remove forms and blend into existing,
6. Form in and pour for one step in center of landing.

Total	11,900.00
-------	-----------

No railing systems are in our pricing for this this proposal .