



**ANYTIME AIR
CONDITIONING, INC.**

To: BCMA / 925 N. Halifax Ave / Daytona Beach, FL

3-20-2020

RE: B level hallway Air Conditioning

We Propose to install a new 2.5-ton air conditioning condensing unit in the block wall between the B level Garage and the maintenance room. A new 3-ton air handler will be mounted on a metal stand against the wall separating the maintenance room and hallway. Refrigerant piping will extend from the new condensing unit to the air handler. Condensate piping will extend down from the air handler to an existing drainpipe. Return air will be drawn through a door grille. The opening in the block wall for the condensing unit and all other block penetrations are by others.

The supply ductwork will be Rigid fiberglass plenums with R-6 Flexible ducts extending to perforated lay-in ceiling diffusers. (2) diffusers will be located north of the double door to the pool deck and (1) diffuser to the south of the door. (2) additional ceiling diffusers will be mounted in the South hallway ceiling as discussed with the manager Bob. We will also consult with Bob regarding the thermostat location.

Electrical power wiring to the condensing unit and air handler should be by an electrician and is not included in our price. Engineered drawings, if required, are not included in our price.

The total price for the new 14 Seer air conditioning system is \$8,850.

Doug Hutson

Anytime Air Conditioning Inc.